



## EMC TEST REPORT

**ETSI EN 301 489-1 V2.2.3 (2019-11)**

**ETSI EN 301 489-3 V2.1.1 (2019-03)**

**EN 55032:2015+A11:2020**

**EN 55035:2017+A11:2020**

**EN IEC 61000-3-2:2019**

**EN 61000-3-3:2013+A1:2019**

**Product:** LoRa Module

**Trade Mark:** B&T 博安通



**Model Name:** Ra-08

**Family Model:** N/A

**Report No.:** S22021800204001

### Prepared for

Shenzhen Ai-Thinker Technology Co., Ltd

410, Block C, Huafeng Smart Innovation Port, Gushu 2nd Road, Gushu Community, Xixiang Street, Baoan District, Shenzhen, China

### Prepared by

Shenzhen NTEK Testing Technology Co., Ltd.

1/F, Building E, Fenda Science Park, Sanwei Community, Xixiang Street  
Bao'an District, Shenzhen 518126 P.R. China

Tel.: 400-800-6106, 0755-2320 0050, 0755-2320 0090


Website: <http://www.ntek.org.cn>

**TEST RESULT CERTIFICATION**

**Applicant's name** ..... : Shenzhen Ai-Thinker Technology Co., Ltd  
**Address** ..... : 410, Block C, Huafeng Smart Innovation Port, Gushu 2nd Road,  
Gushu Community, Xixiang Street, Baoan District, Shenzhen,  
China  
**Manufacturer's Name** ..... : Shenzhen Ai-Thinker Technology Co., Ltd  
**Address** ..... : 410, Block C, Huafeng Smart Innovation Port, Gushu 2nd Road,  
Gushu Community, Xixiang Street, Baoan District, Shenzhen,  
China

**Product description**

**Product name**..... : LoRa Module

**Trademark** ..... : B&T 博安通 , 

**Model and/or type reference** : Ra-08

**Family Model** ..... : N/A

**Standards** ..... : ETSI EN 301 489-1 V2.2.3 (2019-11)  
ETSI EN 301 489-3 V2.1.1 (2019-03)  
EN 55032:2015+A11:2020  
EN 55035:2017+A11:2020  
EN IEC 61000-3-2:2019  
EN 61000-3-3:2013+A1:2019

This device described above has been tested by NTEK, and the test results show that the equipment under test (EUT) is in compliance with the of article 3.1(b) of the Directive 2014/53/EU requirements. And it is applicable only to the tested sample identified in the report.

This report shall not be reproduced except in full, without the written approval of NTEK, this document may be altered or revised by NTEK, personnel only, and shall be noted in the revision of the document.

**Date of Test**.....

**Date (s) of performance of tests**..... Feb 18, 2022 ~ Apr 02, 2022

**Date of Issue**..... Apr 02, 2022

**Test Result**..... **Pass**

**Testing Engineer** :



(Korka Lin)

**Authorized Signatory** :



(Alex Li)

## Table of Contents

## Page

1 . TEST SUMMARY	5
1.1 TEST FACILITY	7
1.2 MEASUREMENT UNCERTAINTY	7
2 . GENERAL INFORMATION	9
2.1 GENERAL DESCRIPTION OF EUT	9
2.2 DESCRIPTION OF TEST MODES	10
2.3 DESCRIPTION OF TEST SETUP	11
2.4 DESCRIPTION TEST PERIPHERAL AND EUT PERIPHERAL	12
2.5 MEASUREMENT INSTRUMENTS LIST	13
3 . EMC EMISSION TEST	18
3.1 CONDUCTED EMISSION MEASUREMENT	18
3.1.1 POWER LINE CONDUCTED EMISSION	18
3.1.2 TEST PROCEDURE	19
3.1.3 TEST SETUP	19
3.1.4 EUT OPERATING CONDITIONS	19
3.1.5 TEST RESULTS	20
3.2 RADIATED EMISSION MEASUREMENT	22
3.2.1 LIMITS OF RADIATED EMISSION MEASUREMENT	22
(Below 1000MHz)	22
3.2.2 LIMITS OF RADIATED EMISSION MEASUREMENT	22
3.2.3 TEST PROCEDURE	22
3.2.4 TEST SETUP	23
3.2.5 EUT OPERATING CONDITIONS	23
3.2.6 TEST RESULTS	24
3.2.7 TEST RESULTS (1000~6000MHz)	26
3.3 HARMONICS CURRENT	27
3.3.1 LIMITS OF HARMONICS CURRENT	27
3.3.1.1 TEST PROCEDURE	28
3.3.1.2 EUT OPERATING CONDITIONS	28
3.3.1.3 TEST SETUP	28
3.3.2 TEST RESULTS	29
3.4 VOLTAGE FLUCTUATION AND FLICKERS	30
3.4.1 LIMITS OF VOLTAGE FLUCTUATION AND FLICKERS	30
3.4.1.1 TEST PROCEDURE	30
3.4.1.2 EUT OPERATING CONDITIONS	30
3.4.1.3 TEST SETUP	31
3.4.2 TEST RESULTS	32

Table of Contents	Page
4 . EMC IMMUNITY TEST	33
4.1 STANDARD COMPLIANCE/SERVIRITY LEVEL/CRITERIA	33
4.1.1 PERFORMANCE CRITERIA	33
4.2 GENERAL PERFORMANCE CRITERIA TEST SETUP	34
4.3 ESD TESTING	35
4.3.1 TEST SPECIFICATION	35
4.3.2 TEST PROCEDURE	35
4.3.3 TEST SETUP	36
4.3.4 TEST RESULTS	37
4.4 RS TESTING	38
4.4.1 TEST SPECIFICATION	38
4.4.2 TEST PROCEDURE	38
4.4.3 TEST SETUP	39
4.4.4 TEST RESULTS	40
4.5 EFT/BURST TESTING	42
4.5.1 TEST SPECIFICATION	42
4.5.2 TEST PROCEDURE	42
4.5.3 TEST SETUP	43
4.5.4 TEST RESULTS	44
4.6 SURGE TESTING	45
4.6.1 TEST SPECIFICATION	45
4.6.2 TEST PROCEDURE	45
4.6.3 TEST SETUP	46
4.6.4 TEST RESULTS	47
4.7 INJECTION CURRENT TESTING	48
4.7.1 TEST SPECIFICATION	48
4.7.2 TEST PROCEDURE	48
4.7.3 TEST SETUP	49
4.7.4 TEST RESULTS	50
4.8 VOLTAGE INTERRUPTION/DIPS TESTING	51
4.8.1 TEST SPECIFICATION	51
4.8.2 TEST PROCEDURE	51
4.8.3 TEST SETUP	51
4.8.4 TEST RESULTS	52
5 . EUT TEST PHOTO	53



## 1. TEST SUMMARY

Test procedures according to the technical standards:

ETSI EN 301 489-1 V2.2.3 (2019-11)

ETSI EN 301 489-3 V2.1.1 (2019-03)

EN 55032:2015+A11:2020

EN 55035:2017+A11:2020

EN IEC 61000-3-2:2019; EN 61000-3-3:2013+A1:2019

EMC Emission				
Standard	Test Item	Limit	Judgment	Remark
EN 55032:2015+A11:2020	Conducted Emission On AC And Telecom Port 150kHz to 30MHz	Class B	PASS	
	Disturbance Voltage at The Antenna Terminals (30MHz To 2150MHz)	-----	N/A	
	Wanted signal and disturbance voltage at the RF output terminals (30MHz To 2150MHz)	-----	N/A	
	Radiated Emission 30MHz to 1000MHz	Class B	PASS	
	Radiated Emission 1GHz to 6GHz	Class B	PASS	
EN IEC 61000-3-2:2019	Harmonic Current Emission	Class A	N/A	
EN 61000-3-3:2013+A1:2019	Voltage Fluctuations & Flicker	-----	N/A	
EMC Immunity				
Section EN 55035:2017+A11:2020	Test Item	Performance Criteria	Judgment	Remark
EN 61000-4-2:2009	Electrostatic Discharge	B	PASS	
EN 61000-4-3:2006+A1:2008+A2:2010	RF electromagnetic field	A	PASS	
EN 61000-4-4:2012	Fast transients	B	N/A	
EN 61000-4-5:2006	Surges	B	N/A	
EN 61000-4-6:2009	Injected Current	A	N/A	
EN 61000-4-11:2004	Volt. Interruptions Volt. Dips	B / C / C NOTE (2)	N/A	

**NOTE:**

- (1) "N/A" denotes test is not applicable in this Test Report
- (2) Voltage dip: 100% reduction – Performance Criteria **B**  
Voltage dip: 30% reduction – Performance Criteria **C**  
Voltage Interruption: 100% Interruption – Performance Criteria **C**
- (3) For client's request and manual description, the test will not be executed.

## 1.1 TEST FACILITY

Shenzhen NTEK Testing Technology Co., Ltd

Add. : 1/F, Building E, Fenda Science Park, Sanwei Community, Xixiang Street, Bao'an District, Shenzhen P.R. China.

FCC FRN Registration Number: 463705; IC Registration Number:9270A-1

CNAS Registration No.:L5516

## 1.2 MEASUREMENT UNCERTAINTY

The reported uncertainty of measurement  $y \pm U$ , where expanded uncertainty  $U$  is based on a standard uncertainty multiplied by a coverage factor of  $k=2$ , providing a level of confidence of approximately **95 %**.

### A. Conducted Measurement :

Test Site	Method	Measurement Frequency Range	U,(dB)	NOTE
NTEKC01	ANSI	150 KHz ~ 30MHz	3.2	

### B. Radiated Measurement :



Test Site	Method	Measurement Frequency Range	U,(dB)	NOTE
NTEKA01	ANSI	30MHz ~ 1000MHz	4.7	
		1GHz ~6GHz	5.0	

[illegible]



## 2. GENERAL INFORMATION

### 2.1 GENERAL DESCRIPTION OF EUT

Equipment	LoRa Module
Trade Mark	 
Model Name	Ra-08
Family Model	N/A
Model Difference	N/A
Frequency Bands:	Band H: 433.050 MHz to 434.790 MHz
Receiver category	1
Power Rating	DC 3.3V form Uart
Battery	N/A
Antenna Designation:	Spring Antenna
Connecting I/O Port(s)	Please refer to the User's Manual
Hardware Version	V1.1
Software Version	V1.1.0

Note:

1. For a more detailed features description, please refer to the manufacturer's specifications or the User's Manual.

## 2.2 DESCRIPTION OF TEST MODES

To investigate the maximum EMI emission characteristics generated from EUT, the test system was pre-scanning tested based on the consideration of following EUT operation mode or test configuration mode which possibly have effect on EMI emission level. Each of these EUT operation mode(s) or test configuration mode(s) mentioned above was evaluated respectively.

For Conducted Test	
Final Test Mode	Description
Mode 1	Working
Mode 2	SRD Lora Link

For Conducted Test	
Final Test Mode	Description
Mode 1	Working


For Radiated Test	
Final Test Mode	Description
Mode 1	Working

For EMS Test	
Final Test Mode	Description
Mode 1	Working
Mode 2	SRD Lora Link


NOTE: The test modes were carried out for all operation modes. The final test mode of the EUT was the worst test mode for EMI, and its test data was showed.

## 2.3 DESCRIPTION OF TEST SETUP

CE




RE



## 2.4 DESCRIPTION TEST PERIPHERAL AND EUT PERIPHERAL

The EUT has been tested as an independent unit together with other necessary accessories or support units. The following support units or accessories were used to form a representative test configuration during the tests.

Item	Equipment	Mfr/Brand	Model/Type No.	Series No.	Note
E-1	LoRa Module	B&T 博安通 , 	Ra-08	N/A	EUT
E-2	DC Source	N/A	N/A	N/A	

Item	Type	Shielded Type	Ferrite Core	Length	Note
C-1	Power Cable	NO	NO	1.2m	

## Note:

- (1) The support equipment was authorized by Declaration of Confirmation.
- (2) For detachable type I/O cable should be specified the length in cm in 『Length』 column.
- (3) “YES” is means “shielded” “with core”; “NO” is means “unshielded” “without core”.

## 2.5 MEASUREMENT INSTRUMENTS LIST

### 2.5.1 CONDUCTED TEST SITE 2.5.1 CONDUCTED EMISSION

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Last calibration	Calibrated until	Calibration period
1	Test Cable	N/A	C01	N/A	May. 11, 2020	May. 10, 2023	3 years
2	Test Cable	N/A	C02	N/A	May. 11, 2020	May. 10, 2023	3 years
3	Test Cable	N/A	C03	N/A	May. 11, 2020	May. 10, 2023	3 years
4	Pulse Limiter	SCHWARZBECK	VTSD 9561F	9716	Apr. 27, 2021	Apr. 26, 2022	1 year
5	50Ω Switch	ANRITSU CORP	MP59B	6200983704	May 11, 2020	May 10, 2023	3 year
6	EMI Test Receiver	R&S	ESCI	101160	Apr. 27, 2021	Apr. 26, 2022	1 year
7	Universal radio communication tester	R&S	CMU200	1100.008.02	Apr. 27, 2021	Apr. 26, 2022	1 year
8	Wideband Radio Communication Tester Specifications	R&S	CMW500	148500	Jul. 01, 2021	Jun. 30, 2022	1 year
9	LISN	SCHWARZBECK	NNLK 8129	8129245	Apr. 27, 2021	Apr. 26, 2022	1 year
10	LISN	R&S	ENV216	101313	Apr. 27, 2021	Apr. 26, 2022	1 year

### 2.5.2 RADIATED TEST SITE

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Last calibration	Calibrated until	Calibration period
1	Antenna Mast	EM	SC100_1	N/A	N/A	N/A	N/A
2	Turn Table	EM	SC100	060531	N/A	N/A	N/A
3	EMI Test Receiver	R&S	ESCI-7	101318	Apr. 27, 2021	Apr. 26, 2022	1 year
4	50Ω Switch	Anritsu Corp	MP59B	6200983705	May 11, 2020	May 10, 2023	1 year
5	Spectrum Analyzer	Aglient	E4407B	MY45108040	Apr. 27, 2021	Apr. 26, 2022	1 year
6	Universal radio communication tester	R&S	CMU200	1100.008.02	Apr. 27, 2021	Apr. 26, 2022	1 year
7	Wideband Radio Communication Tester Specifications	R&S	CMW500	148500	Jul. 01, 2021	Jun. 30, 2022	1 year
8	Test Cable	N/A	R-01	N/A	Aug. 06, 2019	Aug. 05, 2022	3 years
9	Test Cable	N/A	R-02	N/A	Aug. 06, 2019	Aug. 05, 2022	3 years
10	Bilog Antenna	TESEQ	CBL6111D	31216	Apr. 27, 2021	Apr. 26, 2022	1 year
11	Horn Antenna	EM	EM-AH-10180	2011071402	Apr. 27, 2021	Apr. 26, 2022	1 year
12	Amplifier	EMC	EMC051835SE	980246	Jul. 01, 2021	Jun. 30, 2022	1 year



### 2.5.3 HARMONICS AND FILCK

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Last calibration	Calibrated until	Calibration period
1	Harmonic & Flicker	EM TEST	DPA500	0303-04	Apr. 27, 2021	Apr. 26, 2022	1 year
2	AC Power Source	EM TEST	ACS500	0203-01	Apr. 27, 2021	Apr. 26, 2022	1 year
3	Universal radio communication tester	R&S	CMU200	1100.008.0 2	Apr. 27, 2021	Apr. 26, 2022	1 year
4	Wideband Radio Communication Tester Specifications	R&S	CMW500	148500	Jul. 01, 2021	Jun. 30, 2022	1 year

### 2.5.4 ESD

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Last calibration	Calibrated until	Calibration period
1	Universal radio communication tester	R&S	CMU200	1100.008.0 2	Apr. 27, 2021	Apr. 26, 2022	1 year
2	Wideband Radio Communication Tester Specifications	R&S	CMW500	148500	Apr. 27, 2021	Apr. 26, 2022	1 year
3	Electrostatic Discharge Generator	Lioncel	ESD-203B	ESD203B0 150402	Jul. 01, 2021	Jun. 30, 2022	1 year

## 2.5.5 RS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Last calibration	Calibrated until	Calibration period
1	Universal radio communication tester	R&S	CMU200	1100.008.02	Apr. 27, 2021	Apr. 26, 2022	1 year
2	Wideband Radio Communication Tester Specifications	R&S	CMW500	148500	Jul. 01, 2021	Jun. 30, 2022	1 year
3	Audio Power Amplifier	Brüel & Kjær	4602B	2185667	Apr. 27, 2021	Apr. 26, 2022	1 year
4	Mouth Simulator	Brüel & Kjær	2669	2143265	Apr. 27, 2021	Apr. 26, 2022	1 year
5	Sound Calibrator	Brüel & Kjær	4185	2194825	Apr. 27, 2021	Apr. 26, 2022	1 year
6	1/2" Pressure-field Microphone	Brüel & Kjær	735	2641678	Apr. 27, 2021	Apr. 26, 2022	1 year
7	Telephone Test Head	Brüel & Kjær	4185	2631728	Apr. 27, 2021	Apr. 26, 2022	1 year
8	Audio Analyzer	R&S	UPV	100419	Apr. 27, 2021	Apr. 26, 2022	1 year
9	Ear Simulator for Telephonometry	Brüel & Kjær	4185	2553612	Apr. 27, 2021	Apr. 26, 2022	1 year
10	Bilog Antenna	ETS	3142E(Frequency range 30MHz to 6 GHz)	00214344	Jul. 01, 2021	Jun. 30, 2022	1 year
11	Broadband Amplifier	AR	60S1G6	0350414	Jul. 01, 2021	Jun. 30, 2022	1 year
12	PSG Analog Signal Generator	Agilent	E8257D	MY51110112	Jul. 01, 2021	Jun. 30, 2022	1 year
13	Power Amplifier	rflight	NTWPA-00810200	17063153	Jul. 01, 2021	Jun. 30, 2022	1 year
14	Power Amplifier	AR	25S1G4A	308598	Jul. 01, 2021	Jun. 30, 2022	1 year
15	Power Meter	Agilent	E4419B	MY45102538	Jul. 01, 2021	Jun. 30, 2022	1 year
16	Power Sensor	Agilent	E9301A	MY41495644	Jul. 01, 2021	Jun. 30, 2022	1 year
17	Power Sensor	Agilent	E9301A	US39212148	Jul. 01, 2021	Jun. 30, 2022	1 year

## 2.5.6 SURGE, EFT/BURST, VOLTAGE INTERRUPTION/DIPS

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Last calibration	Calibrated until	Calibration period
1	Surge Generator	EVERFINE	EMS61000-5A-V1	1101002	Apr. 27, 2021	Apr. 26, 2022	1 year
2	DIPS Generator	EVERFINE	EMS61000-11K	1011002	Apr. 27, 2021	Apr. 26, 2022	1 year
3	EFT/B Generator	EVERFINE	EMS61000-4A-V2	1012005	Apr. 27, 2021	Apr. 26, 2022	1 year
4	Universal radio communication tester	R&S	CMU200	1100.008.02	Apr. 27, 2021	Apr. 26, 2022	1 year
5	Wideband Radio Communication Tester Specifications	R&S	CMW500	148500	Jul. 01, 2021	Jun. 30, 2022	1 year

### 2.5.7 INJECTION CURRENT

Item	Kind of Equipment	Manufacturer	Type No.	Serial No.	Last calibration	Calibrated until	Calibration period
1	Attenuator	TESEQ	ATN 6075	38411	N/A	N/A	N/A
2	RF Cable	TESEQ	RF Cable	N/A	N/A	N/A	N/A
3	Signal Generator	R&S	SML03	100954	Apr. 27, 2021	Apr. 26, 2022	1 year
4	Power Amplifier	TESEQ	CBA 230M-080	T44376	Apr. 27, 2021	Apr. 26, 2022	1 year
5	EM Clamp	FCC	F-203I-23M M	504	Apr. 27, 2021	Apr. 26, 2022	1 year
6	Audio Power Amplifier	Brüel & Kjær	4602B	2185667	Apr. 27, 2021	Apr. 26, 2022	1 year
7	Mouth Simulator	Brüel & Kjær	2669	2143265	Apr. 27, 2021	Apr. 26, 2022	1 year
8	Sound Calibrator	Brüel & Kjær	4185	2194825	Apr. 27, 2021	Apr. 26, 2022	1 year
9	1/2" Pressure-field Microphone	Brüel & Kjær	735	2641678	Apr. 27, 2021	Apr. 26, 2022	1 year
10	Audio Analyzer	R&S	UPV	100419	Apr. 27, 2021	Apr. 26, 2022	1 year
11	Ear Simulator for Telephonometry	Brüel & Kjær	4185	2553612	Apr. 27, 2021	Apr. 26, 2022	1 year
12	Telephone Test Head	Brüel & Kjær	4185	2631728	Apr. 27, 2021	Apr. 26, 2022	1 year
13	Universal radio communication tester	R&S	CMU200	1100.008.02	Apr. 27, 2021	Apr. 26, 2022	1 year
14	Wideband Radio Communication Tester Specifications	R&S	CMW500	148500	Jul. 01, 2021	Jun. 30, 2022	1 year
15	Coupling and Decoupling Network	TESEQ	CDN M016	38722	Jul. 01, 2021	Jun. 30, 2022	1 year

### 3. EMC EMISSION TEST

#### 3.1 CONDUCTED EMISSION MEASUREMENT

##### 3.1.1 POWER LINE CONDUCTED EMISSION (Frequency Range 150KHz-30MHz)

FREQUENCY (MHz)	Class A (dBuV)		Class B (dBuV)	
	Quasi-peak	Average	Quasi-peak	Average
0.15 -0.5	79.00	66.00	66 - 56 *	56 - 46 *
0.50 -5.0	73.00	60.00	56.00	46.00
5.0 -30.0	73.00	60.00	60.00	50.00

Note:

- (1) The tighter limit applies at the band edges.
- (2) The limit of " \* " marked band means the limitation decreases linearly with the logarithm of the frequency in the range.

The following table is the setting of the receiver


Receiver Parameters	Setting
Attenuation	10 dB
Start Frequency	0.15 MHz
Stop Frequency	30 MHz
IF Bandwidth	9 kHz



### 3.1.2 TEST PROCEDURE

- The EUT was placed 0.8 meters from the horizontal ground plane with EUT being connected to the power mains through a line impedance stabilization network (LISN). All other support equipments powered from additional LISN(s). The LISN provide 50 Ohm/ 50uH of coupling impedance for the measuring instrument.
- Interconnecting cables that hang closer than 40 cm to the ground plane shall be folded back and forth in the center forming a bundle 30 to 40 cm long.
- I/O cables that are not connected to a peripheral shall be bundled in the center. The end of the cable may be terminated, if required, using the correct terminating impedance. The overall length shall not exceed 1 m.
- LISN at least 80 cm from nearest part of EUT chassis.
- For the actual test configuration, please refer to the related Item –EUT Test Photos.

### 3.1.3 TEST SETUP



**Note: 1.Support units were connected to second LISN.**

**2.Both of LISNs (AMN) are 80 cm from EUT and at least 80 from other units and other metal planes**

### 3.1.4 EUT OPERATING CONDITIONS

The EUT tested system was configured as the statements of 2.3 Unless otherwise a special operating condition is specified in the follows during the testing.


## 3.1.5 TEST RESULTS

EUT:	LoRa Module	Model Name :	Ra-08
Temperature:	26 °C	Relative Humidity:	54%
Pressure:	1010 hPa	Polarization :	L
Test Voltage:	DC 3.3V	Test Mode:	Mode 1

Frequency (MHz)	Meter Reading (dBμV)	Factor (dB)	Emission Level (dBμV)	Limits (dBμV)	Margin (dB)	Remark
1.9220	7.84	9.76	17.60	56.00	-38.40	QP
1.9220	-3.58	9.76	6.18	46.00	-39.82	AVG
2.7420	6.71	9.72	16.43	56.00	-39.57	QP
2.7420	-4.40	9.72	5.32	46.00	-40.68	AVG
3.9420	6.52	9.67	16.19	56.00	-39.81	QP
3.9420	-4.49	9.67	5.18	46.00	-40.82	AVG
10.3339	7.75	9.72	17.47	60.00	-42.53	QP
10.3339	-3.76	9.72	5.96	50.00	-44.04	AVG
22.3900	23.11	9.86	32.97	60.00	-27.03	QP
22.3900	7.90	9.86	17.76	50.00	-32.24	AVG
27.5020	18.37	9.87	28.24	60.00	-31.76	QP
27.5020	4.20	9.87	14.07	50.00	-35.93	AVG

Remark:

1. All readings are Quasi-Peak and Average values.
2. Factor = Insertion Loss + Cable Loss.
3. Emission level=Meter Reading+factor; Margin=Emission level-Limits




EUT:	LoRa Module	Model Name :	Ra-08
Temperature:	26 °C	Relative Humidity:	54%
Pressure:	1010 hPa	Polarization :	N
Test Voltage:	DC 3.3V	Test Mode:	Mode 1

Frequency (MHz)	Meter Reading (dBμV)	Factor (dB)	Emission Level (dBμV)	Limits (dBμV)	Margin (dB)	Remark
1.1140	7.89	9.74	17.63	56.00	-38.37	QP
1.1140	-3.87	9.74	5.87	46.00	-40.13	AVG
1.4220	7.02	9.71	16.73	56.00	-39.27	QP
1.4220	-3.92	9.71	5.79	46.00	-40.21	AVG
1.7220	6.27	9.69	15.96	56.00	-40.04	QP
1.7220	-3.21	9.69	6.48	46.00	-39.52	AVG
3.4540	6.79	9.74	16.53	56.00	-39.47	QP
3.4540	-4.10	9.74	5.64	46.00	-40.36	AVG
4.7419	6.37	9.78	16.15	56.00	-39.85	QP
4.7419	-4.69	9.78	5.09	46.00	-40.91	AVG
22.7380	24.36	9.79	34.15	60.00	-25.85	QP
22.7380	8.57	9.79	18.36	50.00	-31.64	AVG

Remark:

1. All readings are Quasi-Peak and Average values.
2. Factor = Insertion Loss + Cable Loss.
3. Emission level=Meter Reading+factor; Margin=Emission level-Limits



Note: The test modes were carried out for all operation modes. The worst test mode for test data was showed in the report.

### 3.2 RADIATED EMISSION MEASUREMENT

#### 3.2.1 LIMITS OF RADIATED EMISSION MEASUREMENT (Below 1000MHz)

FREQUENCY (MHz)	Class A		Class B	
	At 10m	At 3m	At 10m	At 3m
	dBuV/m	dBuV/m	dBuV/m	dBuV/m
30 – 230	40	50	30	40
230 – 1000	47	57	37	47

#### 3.2.2 LIMITS OF RADIATED EMISSION MEASUREMENT (Above 1000MHz)

FREQUENCY (MHz)	Class A (at 3m) dBuV/m		Class B (at 3m) dBuV/m	
	Peak	Avg	Peak	Avg
1000-3000	76	56	70	50
3000-6000	80	60	74	54

Notes:


- (1) The limit for radiated test was performed according to as following:  
EN 55032.
- (2) The tighter limit applies at the band edges.
- (3) Emission level (dBuV/m)=20log Emission level (uV/m).

#### 3.2.3 TEST PROCEDURE


- a. The measuring distance of at 3 m shall be used for measurements at frequency up to 1GHz. For frequencies above 1GHz, any suitable measuring distance may be used.
- b. The EUT was placed on the top of a rotating table 0.8 meters above the ground at a 10 meter open area test site. The table was rotated 360 degrees to determine the position of the highest radiation.
- c. The height of the equipment or of the substitution antenna shall be 0.8 m; the height of the test antenna shall vary between 1 m to 4 m. Both horizontal and vertical polarizations of the antenna are set to make the measurement.
- d. The initial step in collecting conducted emission data is a spectrum analyzer peak detector mode pre-scanning the measurement frequency range. Significant peaks are then marked and then Quasi Peak detector mode re-measured, above 1G Average detector mode will be instead.
- e. If the Peak Mode measured value compliance with and lower than Quasi Peak Mode Limit, the EUT shall be deemed to meet QP(AV) Limits and then no additional QP Mode measurement performed.
- f. For the actual test configuration, please refer to the related Item –EUT Test Photos.

### 3.2.4 TEST SETUP

#### (A) Radiated Emission Test Set-Up Frequency Below 1 GHz



#### (B) Radiated Emission Test Set-Up Frequency Above 1GHz



### 3.2.5 EUT OPERATING CONDITIONS

The EUT tested system was configured as the statements of **2.3** Unless otherwise a special operating condition is specified in the follows during the testing.




### 3.2.6 TEST RESULTS

EUT:	LoRa Module	Model Name :	Ra-08
Temperature:	24 °C	Relative Humidity:	54%
Pressure:	1010 hPa	Polarization :	Horizontal
Test Voltage:	DC 3.3V	Test Mode:	Mode 1

Frequency (MHz)	Meter Reading (dBμV)	Factor (dB)	Emission Level (dBμV/m)	Limits (dBμV/m)	Margin (dB)	Remark
125.0066	9.10	15.31	24.41	40.00	-15.59	QP
148.9625	9.62	16.63	26.25	40.00	-13.75	QP
194.4534	11.51	17.03	28.54	40.00	-11.46	QP
399.0302	6.87	24.75	31.62	47.00	-15.38	QP
670.4892	8.14	28.04	36.18	47.00	-10.82	QP
900.1473	10.12	31.12	41.24	47.00	-5.76	QP

Remark:

1. Factor = Antenna Factor + Cable Loss – Pre-amplifier.




EUT:	LoRa Module	Model Name:	Ra-08
Temperature:	24 °C	Relative Humidity:	54%
Pressure:	1010 hPa	Polarization :	Vertical
Test Voltage:	DC 3.3V	Test Mode:	Mode 1

Frequency	Meter Reading	Factor	Emission Level	Limits	Margin	Remark
(MHz)	(dBμV)	(dB)	(dBμV/m)	(dBμV/m)	(dB)	
89.5899	6.39	14.44	20.83	40.00	-19.17	QP
163.1818	6.18	16.95	23.13	40.00	-16.87	QP
290.0172	6.81	20.19	27.00	47.00	-20.00	QP
401.8385	5.72	24.80	30.52	47.00	-16.48	QP
574.6258	7.13	27.26	34.39	47.00	-12.61	QP
752.7432	7.34	29.29	36.63	47.00	-10.37	QP

Remark:

1. Factor = Antenna Factor + Cable Loss – Pre-amplifier.



### 3.2.7 TEST RESULTS (1000~6000MHz)

EUT:	LoRa Module	Model Name:	Ra-08
Temperature:	24 °C	Relative Humidity:	54%
Test Power:	DC 3.3V	Test Mode:	Mode 1

Polar (H/V)	Frequency	Meter Reading	Factor	Emission Level	Limits	Margin	Remark
	(MHz)	(dBμV)	(dB)	(dBμV/m)	(dBμV/m)	(dB)	
V	1302.499	40.38	0.03	40.41	70.00	-29.59	peak
V	1587.500	39.46	0.51	39.97	70.00	-30.03	peak
V	2300.000	39.57	0.89	40.46	70.00	-29.54	peak
V	2787.500	39.83	1.78	41.61	70.00	-28.39	peak
V	4250.000	37.98	4.36	42.34	74.00	-31.66	peak
V	5937.500	35.89	6.46	42.35	74.00	-31.65	peak
H	1450.000	40.79	0.43	41.22	70.00	-28.78	peak
H	1700.000	39.89	0.51	40.40	70.00	-29.60	peak
H	2487.500	39.07	1.24	40.31	70.00	-29.69	peak
H	2950.000	39.59	2.44	42.03	70.00	-27.97	peak
H	4250.000	38.33	4.36	42.69	74.00	-31.31	peak
H	4987.500	36.75	5.40	42.15	74.00	-31.85	peak

**Remark:**

Emission Level= Meter Reading+ Factor, Margin= Emission Level - Limit

Note: The test modes were carried out for all operation modes. The worst test mode for test data was showed in the report.

### 3.3 HARMONICS CURRENT

#### 3.3.1 LIMITS OF HARMONICS CURRENT

Harmonic Current Test Limit (Class C)

Harmonic order (n)	Maximum permissible harmonic current Expressed as a percentage of the input Current at the fundamental frequency (%)
2	2
3	$30\lambda$
5	10
7	7
9	5
$15 \leq n \leq 39$ (odd harmonics only)	3
<b>Remark:</b> $\lambda$ is the circuit power factor	

Note: Reference standard of the table above: EN61000-3-2.

### 3.3.1.1 TEST PROCEDURE

a. The EUT was placed on the top of a wooden table 0.8 meters above the ground and operated to produce the maximum harmonic components under normal operating conditions.

b. The classification of EUT is according to section 5 of EN 61000-3-2. The EUT is classified as follows:

Class A: Balanced three-phase equipment, Household appliances excluding equipment as Class D, Tools excluding portable tools, Dimmers for incandescent lamps, audio equipment, equipment not specified in one of the three other classes.

Class B: Portable tools. Portable tools.; Arc welding equipment which is not professional equipment.

Class C: Lighting equipment.


Class D: Equipment having a specified power less than or equal to 600W of the following types: Personal computers and personal computer monitors and television receivers.

c. The correspondent test program of test instrument to measure the current harmonics emanated from EUT is chosen. The measure time shall be not less than the time necessary for the EUT to be exercised.

### 3.3.1.2 EUT OPERATING CONDITIONS

The EUT tested system was configured as the statements of **2.3** Unless otherwise a special operating condition is specified in the follows during the testing.

### 3.3.1.3 TEST SETUP





## 3.3.2 TEST RESULTS

EUT:	LoRa Module	Model Name:	Ra-08
Temperature:	25 °C	Relative Humidity:	45%
Pressure:	1010 hPa	Test Mode:	N/A
Test Power:	N/A		

Note: The active input power of the EUT is less than 75 W. No limits apply for equipment with an active input power up to and including 75W.

### 3.4 VOLTAGE FLUCTUATION AND FLICKERS

#### 3.4.1 LIMITS OF VOLTAGE FLUCTUATION AND FLICKERS

Test items	Limits(EN61000-3-3)	Descriptions
$P_{st}$	$\leq 1.0$ , $T_p=10\text{min}$	short-term flicker indicator
$P_{lt}$	$\leq 0.65$ , $T_p=2\text{h}$	long-term flicker indicator
$d_c$	$\leq 3.3\%$	relative steady-state voltage change
$d_{max}$	$\leq 4\%$ (or $6\%$ <sup>Note(1)</sup> , $7\%$ <sup>Note(2)</sup> )	maximum relative voltage change:
$d_{(t)}$	$\leq 3.3\%$ , more than 500ms	relative voltage change characteristic

Note:

1. 6 % for equipment which is:
  - a. switched manually, or
  - b. switched automatically more frequently than twice per day, and also has either a delayed restart (the delay being not less than a few tens of seconds), or manual restart, after a power supply interruption.
2. 7 % for equipment which is
  - a. attended whilst in use (for example: hair dryers, vacuum cleaners, kitchen equipment such as mixers, garden equipment such as lawn mowers, portable tools such as electric drills), or
  - b. switched on automatically, or is intended to be switched on manually, no more than twice per day, and also has either a delayed restart (the delay being not less than a few tens of seconds) or manual restart, after a power supply interruption.

##### 3.4.1.1 TEST PROCEDURE

###### a. Harmonic Current Test:

Test was performed according to the procedures specified in Sub-clause 6.2 of IEC/EN 61000-3-2 depend on which standard adopted for compliance measurement.

###### b. Fluctuation and Flickers Test:


Tests was performed according to the Test Conditions/Assessment of Voltage Fluctuations specified in Clause 6.0/4.0 of IEC/EN 61000-3-3 depend on which standard adopted for compliance measurement.

c. All types of harmonic current and/or voltage fluctuation in this report are assessed by direct measurement using flicker-meter.

##### 3.4.1.2 EUT OPERATING CONDITIONS

The EUT tested system was configured as the statements of **2.3** Unless otherwise a special operating condition is specified in the follows during the testing.

## 3.4.1.3 TEST SETUP



## 3.4.2 TEST RESULTS

EUT:	LoRa Module	Model Name:	Ra-08
Temperature:	25 °C	Relative Humidity:	45%
Pressure:	1010 hPa	Test Power :	N/A
Note:	N/A		

	EUT values	Limit	Result
Pst	0.028	1.00	PASS
Plt	0.028	0.65	PASS
dc [%]	0.000	3.30	PASS
dmax [%]	0.178	4.00	PASS
Tmax [s]	0.000	0.50	PASS

## 4. EMC IMMUNITY TEST

### 4.1 STANDARD COMPLIANCE/SERVRITY LEVEL/CRITERIA

#### 4.1.1 PERFORMANCE CRITERIA

According to **EN 55035** standard, the general performance criteria as following:

<b>Criterion A</b>	<p>The equipment shall continue to operate as intended without operator intervention. No degradation of performance or loss of function is allowed below a performance level specified by the manufacturer when the equipment is used as intended.</p> <p>The performance level may be replaced by a permissible loss of performance. If the minimum performance level or the permissible performance loss is not specified by the manufacturer, then either of these may be derived from the product description and documentation, and by what the user may reasonably expect from the equipment if used as intended.</p>
<b>Criterion B</b>	<p>After the test, the equipment shall continue to operate as intended without operator intervention. No degradation of performance or loss of function is allowed, after the application of the phenomena below a performance level specified by the manufacturer, when the equipment is used as intended.</p> <p>The performance level may be replaced by a permissible loss of performance. During the test, degradation of performance is allowed. However, no change of operating state or stored data is allowed to persist after the test.</p>
<b>Criterion C</b>	<p>Loss of function is allowed, provided the function is self-recoverable, or can be restored by the operation of the controls by the user in accordance with the manufacturer's instructions.</p> <p>Functions, and/or information stored in non-volatile memory, or protected by a battery backup, shall not be lost.</p>

According to **EN 301489 -3** standard, the general performance criteria as following:

Criteria	During the test	After the test
A	<p>Operate as intended</p> <p>No loss of function</p> <p>No unintentional responses</p>	<p>Operate as intended</p> <p>No loss of function</p> <p>No degradation of performance</p> <p>No loss of stored data or user programmable functions</p>
B	<p>May show loss of function</p> <p>No unintentional responses</p>	<p>Operate as intended</p> <p>Lost function(s) shall be self-recoverable</p> <p>No degradation of performance</p> <p>No loss of stored data or user programmable functions</p>

#### 4.2 GENERAL PERFORMANCE CRITERIA TEST SETUP

The EUT tested system was configured as the statements of 2.3 Unless otherwise a special operating condition is specified in the follows during the testing.



### 4.3 ESD TESTING

#### 4.3.1 TEST SPECIFICATION

Basic Standard:	IEC/EN 61000-4-2
Discharge Impedance:	330 ohm / 150 pF
Required Performance	B
Discharge Voltage:	Air Discharge:2kV/4kV/8kV (Direct) Contact Discharge:2kV/4kV (Direct/Indirect)
Polarity:	Positive & Negative
Number of Discharge:	Air Discharge: min. 20 times at each test point Contact Discharge: min. 200 times in total
Discharge Mode:	Single Discharge
Discharge Period:	1 second minimum

#### 4.3.2 TEST PROCEDURE

The test generator necessary to perform direct and indirect application of discharges to the EUT in the following manner:

- a. Contact discharge was applied to conductive surfaces and coupling planes of the EUT.

During the test, it was performed with single discharges. For the single discharge time between successive single discharges was at least 1 second.

Vertical Coupling Plane (VCP):

The coupling plane, of dimensions 0.5m x 0.5m, is placed parallel to, and positioned at a distance 0.1m from, the EUT, with the Discharge Electrode touching the coupling plane.

The four faces of the EUT will be performed with electrostatic discharge.

Horizontal Coupling Plane (HCP):


The coupling plane is placed under to the EUT. The generator shall be positioned vertically at a distance of 0.1m from the EUT, with the Discharge Electrode touching the coupling plane.

The four faces of the EUT will be performed with electrostatic discharge.

- b. Air discharges at insulation surfaces of the EUT.

It was at least ten single discharges with positive and negative at the same selected point.

#### 4.3.3 TEST SETUP



Note:

##### TABLE-TOP EQUIPMENT

The configuration consisted of a wooden table 0.8 meters high standing on the Ground Reference Plane. The GRP consisted of a sheet of aluminum at least 0.25mm thick, and 2.5 meters square connected to the protective grounding system. A Horizontal Coupling Plane (1.6m x 0.8m) was placed on the table and attached to the GRP by means of a cable with 940k total impedance. The equipment under test, was installed in a representative system as described in section 7 of IEC /EN 61000-4-2, and its cables were placed on the HCP and isolated by an insulating support of 0.5mm thickness. A distance of 1-meter minimum was provided between the EUT and the walls of the laboratory and any other metallic structure.

##### FLOOR-STANDING EQUIPMENT

The equipment under test was installed in a representative system as described in section 7 of IEC/EN 61000-4-2, and its cables were isolated from the Ground Reference Plane by an insulating support of 0.1-meter thickness. The GRP consisted of a sheet of aluminum that is at least 0.25mm thick, and 2.5meters square connected to the protective grounding system and extended at least 0.5 meters from the EUT on all sides.

#### 4.3.4 TEST RESULTS

EUT:	LoRa Module	Model Name:	Ra-08
Temperature:	25 °C	Relative Humidity:	45%
Pressure:	1010 hPa	Test Mode:	Mode 1
Test Power:	DC 3.3V		

Mode	Contact Discharge (Indirect)							Observation	Criterion	Result
Test level (kV)	Test Point	2		4		6				
Test Location		+	-	+	-	+	-			
HCP	Front	P	P	P	P			TT,TR	B	Complies
	Rear	P	P	P	P					
	Left	P	P	P	P					
	Right	P	P	P	P					
VCP	Front	P	P	P	P					
	Rear	P	P	P	P					
	Left	P	P	P	P					
	Right	P	P	P	P					

Note:

- 1) +/- denotes the Positive/Negative polarity of the output voltage.
- 2) In the table: 'P' represents 'PASS'; 'F' represents 'FAIL'.

#### 4.4 RS TESTING

##### 4.4.1 TEST SPECIFICATION

Basic Standard:	IEC/EN 61000-4-3
Required Performance	A
Frequency Range:	80 MHz - 6000 MHz
Field Strength:	3 V/m
Modulation:	1kHz Sine Wave, 80%, AM Modulation
Frequency Step:	1 % of fundamental
Polarity of Antenna:	Horizontal and Vertical
Test Distance:	3 m
Antenna Height:	1.5 m
Dwell Time:	at least 3 seconds

##### 4.4.2 TEST PROCEDURE


The EUT and support equipment, which are placed on a table that is 0.8 meter above ground and the testing was performed in a fully-anechoic chamber.

The testing distance from antenna to the EUT was 3 meters.

The other condition as following manner:

- The field strength level was 3V/m.
- The frequency range is swept from 80 MHz to 6000MHz with the signal 80%amplitude modulated with a 1kHz sine wave. The rate of sweep did not exceed  $1.5 \times 10^{-3}$  decade/s. Where the frequency range is swept incrementally, the step size was 1% of fundamental.
- Sweep Frequency 900 MHz, with the Duty Cycle:1/8 and Modulation: Pulse 217 Hz(if applicable)
- The dwell time at each frequency shall be not less than the time necessary for the EUT to be able to respond.

#### 4.4.3 TEST SETUP



Note:

##### TABLE-TOP EQUIPMENT

The EUT installed in a representative system as described in section 7 of IEC/EN 61000-4-3 was placed on a non-conductive table 0.8 meters in height. The system under test was connected to the power and signal wire according to relevant installation instructions.

##### FLOOR-STANDING EQUIPMENT

The EUT installed in a representative system as described in section 7 of IEC/EN 61000-4-3 was placed on a non-conductive wood support 0.1 meters in height. The system under test was connected to the power and signal wire according to relevant installation instructions.

#### 4.4.4 TEST RESULTS

EUT:	LoRa Module	Model Name:	Ra-08
Temperature:	25 °C	Relative Humidity:	60%
Pressure:	1010 hPa	Test Mode:	Mode1/2
Test Power:	DC 3.3V		

##### Mode 2

Frequency Range (MHz)	RF Field Position	R.F. Field Strength	Azimuth	Observation	Perform. Criteria	Results
80~1000	H / V	3 V/m (rms) AM Modulated 1000Hz, 80%	Front	<b>CT,CR</b>	<b>A</b>	<b>P</b>
			Rear			
			Left			
			Right			

Frequency Range (MHz)	RF Field Position	R.F. Field Strength	Azimuth	Observation	Perform. Criteria	Results
1000~6000	H / V	3 V/m (rms) AM Modulated 1000Hz, 80%	Front	<b>CT,CR</b>	<b>A</b>	<b>P</b>
			Rear			
			Left			
			Right			

##### Note:

1. The exclusion band has not been tested in 80MHz~6GHz.

The exclusion band for immunity testing of equipment operating in the 2,4 GHz band shall be: • lower limit of exclusion band = lowest allocated band edge frequency -120 MHz, i.e. 2 280 MHz; • upper limit of exclusion band = highest allocated band edge frequency +120 MHz, i.e. 2 603,5MHz.

2. "A" stand for, during test, operate as intended no loss of function, no degradation of performance, no unintentional transmissions and after test, no degradation of performance, no loss of function, no loss of stored data or user programmable functions.



## Mode 1

Frequency Range (MHz)	RF Field Position	R.F. Field Strength	Azimuth	Perform. Criteria	Results
80~1000 1000~6000	H / V	3 V/m (rms) AM Modulated 1000Hz, 80%	Front	<b>A</b>	<b>P</b>
			Rear		
			Left		
			Right		

Note: "A" stand for, during test, operate as intended no loss of function, no degradation of performance, no unintentional transmissions and after test, no degradation of performance, no loss of function, no loss of stored data or user programmable functions.

## Note:

- 1) N/A - denotes test is not applicable in this test report.
- 2) There was not any unintentional transmission in standby mode
- 3) In the table: 'P' represents 'PASS'; 'F' represents 'FAIL'.

#### 4.5 EFT/BURST TESTING

##### 4.5.1 TEST SPECIFICATION

Basic Standard:	IEC/EN 61000-4-4
Required Performance	B
Test Voltage:	Power Line:1 kV Signal/Control Line:0.5 KV
Polarity:	Positive & Negative
Impulse Frequency:	5 kHz
Impulse Wave shape :	5/50 ns
Burst Duration:	15 ms
Burst Period:	300 ms
Test Duration:	Not less than 1 min.


##### 4.5.2 TEST PROCEDURE

The EUT and support equipment, are placed on a table that is 0.8 meter above a metal ground plane measured 1m\*1m min. and 0.65mm thick min.

The other condition as following manner:

- The length of power cord between the coupling device and the EUT should not exceed 1 meter.
- Both positive and negative polarity discharges were applied.
- The duration time of each test sequential was 1 minute
- For the actual test configuration, please refer to the related Item –EUT Test Photos.

#### 4.5.3 TEST SETUP



Note:

#### TABLE-TOP EQUIPMENT

The configuration consisted of a wooden table (0.8m high) standing on the Ground Reference Plane. The GRP consisted of a sheet of aluminum (at least 0.25mm thick and 2.5m square) connected to the protective grounding system. A minimum distance of 0.5m was provided between the EUT and the walls of the laboratory or any other metallic structure.

#### FLOOR-STANDING EQUIPMENT

The EUT installed in a representative system as described in section 7 of IEC/EN 61000-4-4 and its cables, were isolated from the Ground Reference Plane by an insulating support that is 0.1-meter thick. The GRP consisted of a sheet of aluminum (at least 0.25mm thick and 2.5m square) connected to the protective grounding system.

#### 4.5.4 TEST RESULTS

EUT:	LoRa Module	Model Name:	Ra-08
Temperature:	25 °C	Relative Humidity:	60%
Pressure:	1010 hPa	Test Power :	DC 3.3V
Test Mode:	Mode 1		

##### Mode 1

Coupling Line		Test level (kV)								Observation	Criterion	Result
		0.5		1		2		4				
		+	-	+	-	+	-	+	-			
AC line	L	P	P	P	P					TT,TR	B	Complies
	N	P	P	P	P							Complies
	PE											
	L+N	P	P	P	P							Complies
	L+PE											
	N+PE											
	L+N+PE											
DC Line												
Signal Line												

Note:

- 1)There was not any unintentional transmission in standby mode
- 2) In the table: 'P' represents 'PASS'; 'F' represents 'FAIL'.

## 4.6 SURGE TESTING

### 4.6.1 TEST SPECIFICATION

Basic Standard:	IEC/EN 61000-4-5
Required Performance	B
Wave-Shape:	Combination Wave 1.2/50 us Open Circuit Voltage 8 /20 us Short Circuit Current
Test Voltage:	Power Line:0.5 kV, 1 kV, 2 kV
Surge Input/Output:	L-N, L-PE, N-PE
Generator Source:	2 ohm between networks
Impedance:	12 ohm between network and ground
Polarity:	Positive/Negative
Phase Angle:	0 /90/180/270°
Pulse Repetition Rate:	1 time / min. (maximum)
Number of Tests:	5 positive and 5 negative at selected points

### 4.6.2 TEST PROCEDURE

#### a. For EUT power supply:

The surge is to be applied to the EUT power supply terminals via the capacitive coupling network. Decoupling networks are required in order to avoid possible adverse effects on equipment not under test that may be powered by the same lines, and to provide sufficient decoupling impedance to the surge wave. The power cord between the EUT and the coupling/decoupling networks shall be 2meters in length (or shorter).


#### b. For test applied to unshielded unsymmetrically operated interconnection lines of EUT:

The surge is applied to the lines via the capacitive coupling. The coupling /decoupling networks shall not influence the specified functional conditions of the EUT. The interconnection line between the EUT and the coupling/decoupling networks shall be 2 meters in length (or shorter).

#### c. For test applied to unshielded symmetrically operated interconnection /telecommunication lines of EUT:

#### d. The surge is applied to the lines via gas arrestors coupling. Test levels below the ignition point of the coupling arrestor cannot be specified. The interconnection line between the EUT and the coupling/decoupling networks shall be 2 meters in length (or shorter).

## 4.6.3 TEST SETUP





#### 4.6.4 TEST RESULTS

EUT:	LoRa Module	Model Name:	Ra-08
Temperature:	25 °C	Relative Humidity:	60%
Pressure:	1010 hPa	Test Power :	DC 3.3V
Test Mode:	Model 1		

##### Mode 1

Coupling Line			Test level								Observation	Criterion	Result
			0.5 kV		1 kV		2 kV		4 kV				
			+	-	+	-	+	-	+	-			
AC line	L-N	0°	P	P	P	P					TT,TR	B	Complies
		90°	P	P	P	P							
		180°	P	P	P	P							
		270°	P	P	P	P							
	L-PE	0°											
		90°											
		180°											
		270°											
	N-PE	0°											
		90°											
		180°											
		270°											
DC Line													
Signal Line													

##### Note:

- 1) There was not any unintentional transmission in standby mode
- 2) In the table: 'P' represents 'PASS'; 'F' represents 'FAIL'.

## 4.7 INJECTION CURRENT TESTING

### 4.7.1 TEST SPECIFICATION

Basic Standard:	IEC/EN 61000-4-6
Required Performance	A
Frequency Range:	0.15 MHz - 80 MHz
Field Strength:	3 Vr.m.s.
Modulation:	1kHz Sine Wave, 80%, AM Modulation
Frequency Step:	1 % of fundamental
Dwell Time:	at least 3 seconds


### 4.7.2 TEST PROCEDURE

The EUT and support equipment, are placed on a table that is 0.8 meter above a metal ground plane measured 1m\*1m min. and 0.65mm thick min.

The other condition as following manner:

- The frequency range is swept from 150 KHz to 80 MHz, with the signal 80%amplitude modulated with a 1kHz sine wave. The rate of sweep did not exceed  $1.5 \times 10^{-3}$  decade/s. Where the frequency range is swept incrementally, the step size was 1% of fundamental.
- The dwell time at each frequency shall be not less than the time necessary for the EUT to be able to respond.

#### 4.7.3 TEST SETUP



#### NOTE:

##### FLOOR-STANDING EQUIPMENT

The equipment to be tested is placed on an insulating support of 0.1 meters height above a ground reference plane. All relevant cables shall be provided with the appropriate coupling and decoupling devices at a distance between 0.1 meters and 0.3 meters from the projected geometry of the EUT on the ground reference plane.

#### 4.7.4 TEST RESULTS

EUT:	LoRa Module	Model Name:	Ra-08
Temperature:	25 °C	Relative Humidity:	60%
Pressure:	1010 hPa	Test Power :	DC 3.3V
Test Mode:	Mode 1/2		

##### Mode 1

Test Ports (Mode)	Freq. Range MHz)	Field Strength	Perform. Criteria	Results
Input/ Output AC. Power Port	0.15 ---80	3V(rms) AM Modulated 1000Hz, 80%	<b>A</b>	<b>P</b>
Input/ Output DC. Power Port	0.15 --- 80		<b>N/A</b>	<b>N/A</b>
Signal Line	0.15 --- 80		<b>N/A</b>	<b>N/A</b>

##### Mode 2

Test Ports (Mode)	Freq. Range MHz)	Field Strength	Observation	Perform. Criteria	Results
Input/ Output AC. Power Port	0.15 ---80	3V(rms) AM Modulated 1000Hz, 80%	<b>CT, CR</b>	<b>A</b>	<b>P</b>
Input/ Output DC. Power Port	0.15 --- 80		<b>N/A</b>	<b>N/A</b>	<b>N/A</b>
Signal Line	0.15 --- 80		<b>N/A</b>	<b>N/A</b>	<b>N/A</b>

## 4.8 VOLTAGE INTERRUPTION/DIPS TESTING


### 4.8.1 TEST SPECIFICATION

Basic Standard:	IEC/EN 61000-4-11
Required Performance	B (For 100% Voltage Dips) C (For 30% Voltage Dips) C (For 100% Voltage Interruptions)
Test Duration Time:	Minimum three test events in sequence
Interval between Event:	Minimum ten seconds
Phase Angle:	0°/45°/90°/135°/180°/225°/270°/315°/360°
Test Cycle:	3 times

### 4.8.2 TEST PROCEDURE

The EUT shall be tested for each selected combination of test levels and duration with a sequence of three dips/interruptions with intervals of 10 s minimum (between each test event). Each representative mode of operation shall be tested. Abrupt changes in supply voltage shall occur at zero crossings of the voltage waveform.

### 4.8.3 TEST SETUP



#### 4.8.4 TEST RESULTS

EUT:	LoRa Module	Model Name:	Ra-08
Temperature:	25 °C	Relative Humidity:	60%
Pressure:	1010 hPa	Test Power :	DC 3.3V
Test Mode:	Mode 1/2		

##### Mode 1

Voltage Reduction	Duration (ms)	Perform Criteria	Results
Voltage dip: 0%	10	<b>B</b>	<b>P</b>
Voltage dip: 0%	20	<b>B</b>	<b>P</b>
Voltage dip: 70%	500	<b>C</b>	<b>P</b>
Voltage interruptions: 0%	5000	<b>C</b>	<b>P</b>


##### Mode 2

Voltage Reduction	Duration (ms)	Observation	Perform Criteria	Results
Voltage dip: 0%	10	<b>TT, TR</b>	<b>B</b>	<b>P</b>
Voltage dip: 0%	20	<b>TT, TR</b>	<b>B</b>	<b>P</b>
Voltage dip: 70%	500	<b>TT, TR</b>	<b>C</b>	<b>P</b>
Voltage interruptions: 0%	5000	<b>TT, TR</b>	<b>C</b>	<b>P</b>




## 5. EUT TEST PHOTO

Radiated Measurement Photos



**Conducted Measurement Photo**



END OF REPORT